



Jason Anderson <jasoande@redhat.com>

OpenShift Virtualization - POC Planning

John Kinney <jkinney@redhat.com>

Thu, May 14, 2026 at 12:55 PM

To: Scott Jobe <Scott.Job@blueyonder.com>

Cc: Dan Wilson <dan.wilson@ineapple.com>, Michael Quick <mquick@redhat.com>, Jason Anderson <jasoande@redhat.com>, Bill Venella <bvenella@redhat.com>, Panindra Balellugari <pbalellu@redhat.com>, Joe Moreno <Joe.Moreno@blueyonder.com>, Todd Bowen <Todd.Bowen@blueyonder.com>, Cristian Garcia <Cristian.Garcia@blueyonder.com>

Thanks Scott!

This is helpful! I have a few follow up questions.

- Is the Proxy performing SSL inspection / intercept?
- For the active-active bond, are you thinking of using an LACP bond, assuming the switches are configured for it?
- Are you currently using only one pair of interfaces in VMware?
 - Only one bonded pair will work for our POC and is supported, but we generally see 2 bonded pairs of interfaces: one for the management network and the other dedicated to VM data traffic. So, I'm just curious if this is based on the POC hardware, or if you are running only 1 pair of interfaces today.
- How long do firewall rules typically take to implement?
 - The OpenShift platform images are hosted in a few Red Hat container registries, so we'll want to make sure we can access them to perform the installation. Depending on how long it takes to implement firewall rules, we may want to get ahead of these requests so we can hit the ground running once you complete your POC work -- provided you have capacity for it as well.
 - Additionally, we may want to consider 3rd party images hosted in different registries, such as Pure / Portworx. This may not be an issue since I believe you're already using that in the current POC, but I wanted to highlight 3rd party images as an additional dependency we may need to consider.

In terms of using 5 nodes.

- 5 nodes will work.
- OpenShift has a few different architectures, but a traditional deployment consists of 3 control plane nodes and N worker nodes based on capacity requirements to run your workloads. Single node, two node, and 3 node "compact" cluster architectures are also available and often used in edge deployments or smaller sites.
- Control plane nodes can be dedicated solely to control plane functions, or they can be "Scheduable" to perform both control plane and worker node roles.
- If only 5 nodes are available, we can use 3 dedicated control plane nodes and 2 worker nodes, or enable Scheduling on the control plane nodes so that all 5 nodes can run user workloads. This can be configured on Day 2, so we don't necessarily need to decide before performing the installation.
- However, I asked because customers often want to see how to scale out the cluster and add a new node. While this isn't included in every POC, it's fairly straightforward to do so I'm happy to include it, we'll just need to plan based on available hardware. Alternatively we can discuss and demo the process instead of including it in the POC as well. We don't necessarily have to decide this now, so we can discuss it more as we get closer to starting the installation.

Thanks!

John Kinney

Application Platform Specialist Solutions Architect

[Red Hat Northeast Region](#)

jkinney@redhat.com

@RedHat Red Hat Red Hat



[Quoted text hidden]